BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No: EE/RRND/Tend/18/2019-20 Date: 02.03.2020

Indet No: BBMP/2019-20/BD/WORK_INDENT40626

SCHEDULE -B

Name of Work: Maintenance of Burial Ground in Bahubali Nagar in ward no 16

Sl.No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	2559.00	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. Complete as per the direction of Engineer in Charge with all lead and Lift	Cum	441.00	Rupees Four Hundred Forty One Only
2	32.25	Providing and laying in position plain cement concrete of mix M10 with OPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregtes @ 0.56cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation,plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications.Complete as per the direction of Engineer in Charge with all lead and Lift	Cum	6009.00	Rupees Six Thousand Nine Only
3	52.05	Providing and laying in position plain cement concrete of mix M20 with cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation,plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Complete as per the direction of Engineer in Charge with all lead and Lift	Cum	6137.00	Rupees Six Thousand One Hundred Thirty Seven Only
4	4.68	Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Complete as per the direction of Engineer in Charge with all lead and Lift	Tonne	80322.00	Rupees Eighty Thousand Three Hundred Twenty Two Only
5	167.10	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specifications. Complete as per the direction of Engineer in Charge with all lead and Lift	Sqm	292.00	Rupees Two Hundred Ninety Two Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned with CamScanner

6	129.20	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specification. Complete as per the direction of Engineer in Charge with all lead and Lift	Sqm	516.00	Rupees Five Hundred Sixteen Only
7	215.89	Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing Complete as per the direction of Engineer in Charge with all lead and Lift	Cum	5202.00	Rupees Five Thousand Two Hundred Two Only
8	33.57	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing Complete as per the direction of Engineer in Charge with all lead and Lift	Cum	6315.00	Rupees Six Thousand Three Hundred Fifteen Only
9	503.15	Providing and constructing precast concrete solid blocks with compressive strength not less than 3.50 newton per sqmm with cement mortar 1 :4 (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x15x20cms. (LxBxH) conforming to I.S : 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing Complete as per the direction of Engineer in Charge with all lead and Lift	Cum	1079.00	Rupees One Thousand Seventy Nine Only
10	193.50	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.Complete as per the direction of Engineer in Charge with all lead and Lift	Sqm	161.00	Rupees One Hundred Sixty One Only
11	1050.00	Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Complete as per the direction of Engineer in Charge with all lead and Lift	Sqm	239.00	Rupees Two Hundred Thirty Nine Only
12	1050.00	Providing and finishing external walls in two coats with waterproof cement paint with primer of approved brand and shade to give an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications with primer. Complete as per the direction of Engineer in Charge with all lead and Lift	Sqm	115.00	Rupees One Hundred Fifteen Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned with CamScanner